

April 19, 1996

CRITICAL ITEMS LIST

PAGE 1

- 1) CIL ITEM : F200-AL-01
- 2) FMEA CODE : F200-AL
- 3) COMPONENT : POGO PRECHARGE PRESSURE SENSOR INTERFACE P18
- 4) PART NUMBER : RE1493
- 5) SYSTEM/SUBSYSTEM : CONTROLLER/F200-YK
- 6) FAILURE MODE : FAILURE OF THE POGO PRECHARGE PRESSURE SENSOR INTERFACE

- 7) PREPARED : SSME RELIABILITY
- 8) APPROVED :
- 9) DATE : 04-19-96
- 10) REVISION/CHANGE : -001/D
- 11) EFFECTIVITY : -05
- 12) HAZARD REFERENCE: : SEE LISTINGS BELOW
- 13) CCRD # : ME3-01-3285

PHASE	FAILURE DESCRIPTION/EFFECT	CRITICALITY
<p>P 4-2</p>	<p>FAILURE OF BOTH QUALIFIED SENSOR INTERFACES OR REMAINING QUALIFIED SENSOR INTERFACE WITHIN MONITOR LIMITS RESULTS IN LOSS OF ENGINE START INHIBIT PROTECTION. LOSS OF VEHICLE DURING START DUE TO HPOTP FAILURE MAY RESULT IF POGO PRECHARGE FLOW IS NOT TERMINATED AND FAILURE IS NOT DETECTED.</p> <p>REDUNDANCY SCREENS: CONTROLLER SYSTEM - ENGINE SYSTEM: UNLIKE REDUNDANCY</p> <p>-----</p> <p>A: PASS. REDUNDANT HARDWARE ITEMS ARE CAPABLE OF CHECKOUT DURING NORMAL GROUND TURNAROUND. B: FAIL. LOSS OF A REDUNDANT HARDWARE ITEM IS NOT DETECTABLE DURING FLIGHT. C: PASS. LOSS OF REDUNDANT HARDWARE ITEMS COULD NOT RESULT FROM A SINGLE CREDIBLE EVENT.</p>	<p>1R HAZARD REF: ME-C15,N</p>
<p>S 4-5</p>	<p>FAILURE OF BOTH QUALIFIED SENSOR INTERFACES OR REMAINING QUALIFIED SENSOR INTERFACE WITHIN FLOW CHECK LIMITS RESULTS IN LOSS OF NCF PROTECTION. LOSS OF VEHICLE DUE TO POGO MAY RESULT IF POGO GOK FLOW IS NOT ESTABLISHED AND FAILURE IS NOT DETECTED.</p> <p>REDUNDANCY SCREENS: CONTROLLER SYSTEM - ENGINE SYSTEM: UNLIKE REDUNDANCY</p> <p>-----</p> <p>A: PASS. REDUNDANT HARDWARE ITEMS ARE CAPABLE OF CHECKOUT DURING NORMAL GROUND TURNAROUND. B: FAIL. LOSS OF A REDUNDANT HARDWARE ITEM IS NOT DETECTABLE DURING FLIGHT. C: PASS. LOSS OF REDUNDANT HARDWARE ITEMS COULD NOT RESULT FROM A SINGLE CREDIBLE EVENT.</p>	<p>1R HAZARD REF: ME-C15,N</p>
<p>C 4-2</p>	<p>FAILURE OF ONE OR BOTH QUALIFIED SENSOR INTERFACES WITHIN MONITOR LIMITS RESULTS IN LOSS OF EMSO MONITORING. LOSS OF VEHICLE DUE TO OXIDIZER PUMP OVERSPEED AND FAILURE MAY RESULT IF POGO POST-CHARGE HELIUM FLOW IS NOT ESTABLISHED AND FAILURE IS NOT DETECTED.</p> <p>REDUNDANCY SCREENS: CONTROLLER SYSTEM - ENGINE SYSTEM: UNLIKE REDUNDANCY</p> <p>-----</p> <p>A: PASS. REDUNDANT HARDWARE ITEMS ARE CAPABLE OF CHECKOUT DURING NORMAL GROUND TURNAROUND. B: FAIL. LOSS OF A REDUNDANT HARDWARE ITEM IS NOT DETECTABLE DURING FLIGHT. C: PASS. LOSS OF REDUNDANT HARDWARE ITEMS COULD NOT RESULT FROM A SINGLE CREDIBLE EVENT.</p>	<p>1R HAZARD REF: ME-G10C,D ME-C1A,C</p>

F-53

CIL ITEM: F200-AL-01

DESIGN

DOCUMENT REF.

ALL CAUSES: INPUT ELECTRONICS: OPEN CIRCUIT IN THE SENSOR INTERFACE (1)

(1) HONEYWELL BLOCK 11
FMEA VOL IV IC-F4

THE POOD PRECHARGE PRESSURE SENSOR INTERFACES ARE REDUNDANT (1). A FAILURE MUST OCCUR IN EACH CONTROLLER CHANNEL (MULTIPLE FAILURE) TO CAUSE LOSS OF FUNCTION (2). THE CONTROLLER (WITH SOFTWARE) IS CONFIGURED TO DETECT AND RESPOND PROPERLY TO OUT OF QUALIFICATION LIMIT FAILURES, IMPLEMENT THE APPROPRIATE REDUNDANCY MANAGEMENT RESPONSE, AND COMMAND A SAFE ENGINE STATE WHEN CONTROLLER REDUNDANCY IS LOST (2). HOWEVER, THE CONTROLLER (WITH SOFTWARE) IS NOT CAPABLE OF DETECTING OR RESPONDING TO A FAILURE WHICH RESULTS IN THE LIMITS BEING MONITORED FAILING WITHIN ENGINE REDLINE LIMITS OR WITHIN NORMAL ENGINE OPERATING CONDITIONS (2).

(1) DSHG8977A1
(2) CP406R0008
3.1.3:3
3.2.1:6.2
3.2.3:2.3
3.2.3:3
3.2.3:4
3.2.3:5
3.2.4

ELECTRICAL, MECHANICAL, AND ELECTROMECHANICAL PARTS FOR THE CIRCUITS INVOLVED IN THIS FUNCTION HAVE BEEN SELECTED FROM THE CLASS 9 OR EQUIVALENT APPROVED PARTS SELECTION LIST (1), DUALITY ASSURANCE AND SCREENING REQUIREMENTS FOR HIGH RELIABILITY MICROCIRCUITS (2), AND THE SPECIFICATION CONTROL DRAWING FOR MICROCIRCUITS, MONOLITHIC SILICON, AND TRANSISTOR-TRANSISTOR LOGIC (TTL) FAMILY OF DEVICES (3). PRIOR TO INSTALLATION ON THE CARD ASSEMBLIES, COMPONENTS ARE SUBJECTED TO A BURN-IN PERIOD WHERE PARTS ARE EXERCISED AT TEMPERATURES IN EXCESS OF NORMAL CONTROLLER OPERATING ENVIRONMENT, BUT LESS THAN COMPONENT MAXIMUM SPECIFIED OPERATING ENVIRONMENT, TO SCREEN FOR INFANT MORTALITY (4). IN ADDITION TO THESE REQUIREMENTS, ALL COMPONENTS ARE DERATED FROM THE MAXIMUM RATING AT OPERATING EXTREMES (5). CLEANLINESS AND ALL PROCESSES USED DURING MANUFACTURE ARE CONTROLLED BY SPECIFICATION REQUIREMENTS (5).

(1) 85M03928,
85M03929
(2) 85M02704
(3) 85M03766
(4) 85M03876
(5) DSHG8977A1

THE CONTROLLER DESIGN MEETS ALL CE) FAIL-OPERATE/FAILSAFE REQUIREMENTS FOR THIS FAILURE MODE (1). REDUNDANT CONTROLLER CHANNEL FUNCTIONS ARE PHYSICALLY SEPARATED WITHIN THE CONTROLLER HOUSING (2). CIRCUITS ARE DESIGNED TO PREVENT BRIDGING (2), ALL EEE PARTS ARE REQUIRED TO HAVE CONFORMAL COATING, AND INTERNAL WIRING IS INSULATED TO PREVENT SHORT CIRCUITS FROM CONDUCTIVE CONTAMINATION (3). ALL ELECTRICAL COMPONENTS ARE CONTAINED WITHIN THE CASE STRUCTURE WHICH IS PRESSURIZED WITH A POSITIVE PRESSURE INERT GAS BACKFILL TO PREVENT CONTAMINATION (2). WHERE APPLICABLE, ELECTROMAGNETIC INTERFERENCE SHIELDING IS PROVIDED AND CIRCUIT INTERCONNECTS USE TWISTED PAIR WIRING (2). ALL CIRCUIT CARDS ARE KEYED TO THEIR RESPECTIVE CONNECTION LOCATIONS TO PRECLUDE IMPROPER INSTALLATION (2). RAMP CLAMPS ARE UTILIZED TO PRECLUDE VIBRATION INDUCED CARD FAILURES (2). DESIGN OF CIRCUIT CARDS AND DETERMINATION OF COPPER PATH TRACE SPACING, WEIGHT, AND WIDTH IS CONTROLLED BY SPECIFICATION (2). EACH UNIT (PRODUCTION AND RECYCLE) IS REQUIRED TO PASS A FUNCTIONAL ACCEPTANCE TEST UNDER ENVIRONMENTAL CONDITIONS BEYOND THOSE SEEN DURING NORMAL FIELD OPERATION WITHOUT DEGRADATION OF HARDWARE LIFE EXPECTANCY (2). A WORST CASE CIRCUIT ANALYSIS WAS PERFORMED TO VERIFY NOMINAL OPERATION AT SPECIFICATION LIMITS (4). AN ANALYSIS WAS PERFORMED BY HONEYWELL TO ASSURE NO SINGLE POINT COMPONENT FAILURES ARE INHERENT TO THE CONTROLLER DESIGN (5).

(1) CPJ20R00038
(2) DSHG8977A1
(3) 85M03928
(4) E524472-01
(5) HONEYWELL BLCK 11
FMEA VOL I

F-54

CIL ITEM: F200-AL-01		DESIGN	DOCUMENT REF.
DESIGN QUALIFICATION TESTING OF THE CONTROLLER ASSEMBLY HAS BEEN PERFORMED INCLUDING: FAULT INSERTION TESTING (1), ASSEMBLY THERMAL CYCLING (2), CASE AND ASSEMBLY VIBRATION TESTING (3), ELECTROMAGNETIC INTERFERENCE AND SUSCEPTIBILITY TESTING (4), ACOUSTICAL NOISE TESTING (5), CASE ULTIMATE PRESSURE TESTING (6), AND ASSEMBLY BREAK OPEN INSPECTION (7).			(1) TR34079282 TR34080202 TR34080258 TR34080259 (2) TR34080203 TR34080207 (3) TR34080204 TR34080205 TR34080206 TR34087499 (4) TR34080209 (5) TR34080210 (6) TR34085021 (7) TR34085022
CIL ITEM: F200-AL-01		INSPECTION AND TEST	DOCUMENT REF.
POSSIBLE CAUSES	SIGNIFICANT CHARACTERISTICS	INSPECTION(S)/TEST(S)	DOCUMENT REF.
ALL CAUSES:	RE1493 - CONTROLLER		RE1493
	ASSEMBLY INTEGRITY	CLEANLINESS REQUIREMENTS ARE VERIFIED PER SPECIFICATION DURING MANUFACTURING OF THE CONTROLLER ASSEMBLY. ENVIRONMENT CONTROLS (TEMPERATURE, HUMIDITY) ARE ENFORCED DURING ASSEMBLY AND TESTING PER SPECIFICATION REQUIREMENTS. TO PREVENT COMPONENT DAMAGE, STATIC ELECTRICAL DISCHARGE POTENTIAL IS CONTROLLED DURING MANUFACTURING PER SPECIFICATION REQUIREMENTS.	RC1493 DSHG8977A1 DSHG8977A1
	MATERIAL INTEGRITY	MATERIAL INTEGRITY IS VERIFIED PER SPECIFICATION REQUIREMENTS.	RC1493

11-55

CIL ITEM: F200-AL-01		INSPECTION AND TEST	
POSSIBLE CAUSES	SIGNIFICANT CHARACTERISTICS	INSPECTION(S)/TEST(S)	DOCUMENT REF.
		PROTECTIVE FINISHES AND MATERIAL SELECTION TO PREVENT DETRIMENTAL EFFECTS FROM ENVIRONMENTAL EXPOSURE, STRESS CORROSION, AND ELECTROLYTIC CORROSION ARE VERIFIED PER SPECIFICATION REQUIREMENTS.	RC1493 MSPC-SPEC-250
		FLAMMABILITY REQUIREMENTS ARE VERIFIED PER SPECIFICATION REQUIREMENTS.	RC1493
	INTEGRITY OF ELECTRONICS	THE FOLLOWING PROCESSES ARE VERIFIED PER SPECIFICATION DURING MANUFACTURING OF THE CARD ASSEMBLIES: <ul style="list-style-type: none"> - CONSTRUCTION OF PRINTED CIRCUIT BOARDS. - INSTALLATION OF TERMINALS. - PLASTICS AND ELASTOMERS FOR ELECTRONIC ENCAPSULATION. - SOLDERED ELECTRICAL CONNECTIONS. - POST-SOLDERING INSPECTION FREE OF SPLATTER AND CONTAMINATION. - ELECTRICAL BONDING. - COMPONENT LEAD AND INTERCONNECTION MATERIAL SELECTION. - FREE OF CONTAMINATION AFTER CONFORMAL COATING. 	RL10005 RL10007 RL10008 RL10009 RL10009 RC1493 B5N03928 RC1493
	WELD INTEGRITY	ALL WELDS ARE VERIFIED TO DRAWING AND SPECIFICATION REQUIREMENTS.	RL10011
	PRE-CLOSEOUT TESTING AND INSPECTION	THE FOLLOWING TESTS ARE PERFORMED AT THE CARD/COMPONENT LEVEL DURING MANUFACTURING: <ul style="list-style-type: none"> - PARTIAL IMPACT NOISE DETECTION (PIND) TEST ON HYBRID MICROCIRCUITS AND CAVITY TYPE DEVICES. - ULTRASONIC SCAN TEST FOR DELAMINATION CERAMIC ON CAPACITORS (CKR05 AND CKR06). - BURN-IN PERIOD FOR ELECTRICAL PARTS. - INSULATION RESISTANCE AND CONTINUITY TEST. - DIELECTRIC WITHSTANDING VOLTAGE. - FUNCTIONAL TEST. - X-RAY OF CONTROLLER INTERNAL CABLES AND WIRES. 	DSHG8977A1 DSHG8977A1 B5N03928 DSHG8977A1 DSHG8977A1 DSHG8977A1 DSHG8977A1

F - 56

CIL ITEM: F200-AL-01		INSPECTION AND TEST	
POSSIBLE CAUSES	SIGNIFICANT CHARACTERISTICS	INSPECTION(S)/TEST(S)	DOCUMENT REF.
		<p>THE FOLLOWING INSPECTIONS ARE PERFORMED ON THE COMPLETED ASSEMBLY PRIOR TO FINAL CLOSURE:</p> <ul style="list-style-type: none"> - INTERNAL AND EXTERNAL CLEANLINESS. - CARD DIMENSIONS ARE VERIFIED AT CARD ASSEMBLY. - CHASSIS CAVITY INSPECTION FOR CONTAMINATION. - ELECTRICAL INTERFACE CONNECTORS. - CARD INSTALLATION AND CONFIGURATION AUDIT. - CONFORMAL COATING OF EEE PARTS. 	<p>RC1493 DSHG8977A1 RC1493 RC1493 DSHG8977A1 85ND3928</p>
	ACCEPTANCE TESTS	<p>THE FOLLOWING TESTS ARE PERFORMED BY HONEYWELL DURING ACCEPTANCE TESTING:</p> <ul style="list-style-type: none"> - HERMETIC SEAL AND PRESSURIZATION PORT LEAK TEST. - FUNCTIONAL TEST INCLUDING: <ul style="list-style-type: none"> - OUTPUT INTERFACE, - CHECKOUT, - OPERATION, - CONTROLLER CHECKOUT. - HIGH TEMPERATURE OPERATION. - LOW TEMPERATURE OPERATION. - VIBRATION TESTING. - FINAL FUNCTIONAL TEST. 	<p>RC1493 RC1493 RC1493 RC1493 RC1493 RC1493 RC1493 RC1493 RC1493</p>
	HOT FIRE ACCEPTANCE TESTING (GREEN RUN)	<p>CONTROLLER OPERATION IS VERIFIED THROUGH ENGINE HOT FIRE ACCEPTANCE TESTING.</p>	<p>RL00461</p>
	HERMETIC SEAL INTEGRITY	<p>INTERNAL PRESSURE IS MONITORED DURING CONTROLLER OPERATION.</p>	<p>OMRSD W41AND.040</p>
	FLIGHT FLOW TESTING	<p>THE FOLLOWING TESTS ARE PERFORMED DURING FLIGHT FLOW VEHICLE PROCESSING AND AFTER ANY MAINTENANCE OR REPLACEMENT:</p> <ul style="list-style-type: none"> - CONTROLLER CHECKOUT. - SENSOR CHECKOUT. - FLIGHT READINESS TEST. - SELF-TEST. 	<p>OMRSD W41AND.035 OMRSD W41AQO.010 OMRSD W41ASO.030-A CP406R0008</p>

F-57

CIL ITEM: F200-AL-01		INSPECTION AND TEST	
POSSIBLE CAUSES	SIGNIFICANT CHARACTERISTICS	INSPECTION(S)/TEST(S)	DOCUMENT REF.
	PRE-FLIGHT CHECKOUT	THE FOLLOWING TESTS ARE PERFORMED DURING LAUNCH COUNTDOWN (LAST TEST): - PRE-CRYO LOADING CHECKOUT INCLUDING CONTROLLER AND SENSORS CHECKOUT. - SELF-TEST.	DMRSD 500FA0.213 CP406R0008
FAILURE HISTORY: COMPREHENSIVE FAILURE HISTORY DATA IS MAINTAINED IN THE PROBLEM REPORTING DATABASE (PRMS/PRACA). REFERENCE: NABA LETTER SA21/88/30B AND ROCKETDYNE LETTER BRRC09761.			

OPERATIONAL USE: NOT APPLICABLE.