

SAA09FY12-006
REV. BB/L: 389.00
SYS: 175-TON
BRIDGE
CRANE, VAB

Critical Item: Resistor, Auxiliary Hoist (2 total)
Find Number: 2RR4A, 2RR4B (1ea)
Criticality Category: 2

AUG 20 1993

SAA No: 09FY12-006	System/Area: 175-Ton Bridge Crane/VAB
NASA	PMN/ K60-0528/
Part No: NA	Name: 175-Ton Bridge Crane/VAB
Mfg/ DIGI-KEY/	Drawing/ 67-K-L-11348/
Part No: P 1.6KW-2	Sheet No: 19

Function: Provides a voltage divider for the +/- 5VDC power source to the potentiometer, R-POT, in the master controller (joystick), 2MC, for input to the generator field DC input controller, 2FC, to allow for auxiliary hoist operation in the fine speed mode.

Critical Failure Mode/Failure Mode No: Fails open/09FY12-006.078

Failure Cause: Contamination, corrosion, fatigue

Failure Effect: No generator field DC input controller excitation voltage in the fine speed mode of operation. No generator field winding voltage. No output from the generator. No hoist motor torque when the command is given, via the master control switch to raise or lower the load while the brakes are released. The load will descend with regenerative braking at 1.7 ft/min (0.34 in/sec) max (based on maximum load capacity of the hoist, in reality this would descend slower). The worst case would be attempting to lift a forward assembly from the stop position, releasing the brakes, the failure occurring, and the effect being the forward assembly descending and striking the VAB floor or platform, resulting in possible damage to a vehicle system. Time to effect: seconds.

ACCEPTANCE RATIONALE

Design:

- 1600 Ohm Resistor
- 5% Metal Oxide Film Resistor
- Resistance tolerance: +/- 5%.
- Meets overload tests in accordance with UL (Underwriters Laboratories) specification #1412 without producing a fire hazard.
- Withstands solvents in accordance with Mil-Std-202E without producing mechanical or electrical damage.

AUG 20 1993

- Temperature coefficient: +/- 100 PPM/°C typ., +/- 200 PPM/°C max.
- Maximum working voltage: 350 volts
- Actual working voltage: 6 volts
- Rated power: 2 watts
- Actual power: 0.0082 watts

Test:

- OMRSD file VI requires verification of proper performance of hoist operational test annually.
- OMI Q3006, Operating Instructions, requires all crane systems be operated briefly in all speeds to verify satisfactory operation before lifting operations.

Inspection:

- OMI Q6003, Maintenance Instructions, requires annual inspection of resistors for deterioration/discoloration caused by corrosion or overheating.

Failure History:

- The PRACA database was researched and no failure data was found on this component in the critical failure mode.
- The GIDEP failure data interchange system was researched and no failure data was found on this component in the critical failure mode.

Operational Use:

- **Correcting Action:**
 - 1) The failures can be recognized via the Selsyn (positions change) that is in view of both operators.
 - 2) When the failure indication is noticed, the operator can stop all crane operations by returning the master control switch to neutral, or pressing the E-Stop button.
 - 3) Operators are trained and certified to operate these cranes and know and understand what to do if a failure indication is present.
 - 4) During all critical lifts, there is at least one remote Emergency Stop (E-Stop) operator observing the load lift, and can stop the crane if a failure indication is noticed.
- **Timeframe:**
 - Estimated operator reaction time is 3 to 10 seconds.