

CRITICAL ITEMS LIST

PROJECT: SRMS
 ASS'Y NOMENCLATURE: DEC PANEL

SYSTEM: DEC SUBSYSTEM
 ASS'Y P/N: 51102501

SHEET: 1

ITEM REF.	REV.	NAME, QTY, & DRAWING REF. DESIGNATION	FAILURE MODE AND CAUSE	FAILURE EFFECT OR END ITEM	PLAN 7 FUNC. 1/1 CRITICALITY	RATIONALE FOR ACCEPTANCE
1130	0	DIRECT DRIVE COMMANDS QTY-1 REF. SIGNAL CIRCUIT EDB7919	MODE: LOSS OF 12.4V SIGNAL. CAUSE(S): (1) ZENER S/C (COPPER ZENER)	12.4V SIGNAL (+ DRIVE) WILL BE SHORTED TO 6.2V. JOSHMG WILL DRIVE 'NEG' FOR 'POS' OR 'NEG' COMMAND. WORST CASE ----- UNEXPECTED MOTION. SMOGG JOINT DIRECTION. UNANNOUNCED. CREW ACTION REQ. REDUNDANT PATHS REMAINING ----- N/A		DESIGN FEATURES ----- THE REQUIRED SIGNALS ARE DERIVED FROM TWO 6.2 VOLT ZENER BYONES. THE DIODES ARE SERIES CONNECTED WITH A 750 OHM RESISTOR ACROSS THE 28VDC POWER SUPPLY. THE DIODES ARE PROTECTED AGAINST VOLTAGE TRANSIENTS BY A 0.1 UF CERAMIC CAPACITOR. WORST CASE POWER STRESS LEVEL IN EACH DIODE IS APPROX. 32 PER CENT OF RATED. POWER DISSIPATION IN THE RESISTOR IS APPROX. 46 PER CENT OF RATED. VOLTAGE STRESS LEVEL FOR THE CAPACITOR IS 20 PER CENT OF RATED. EEE PARTS HAVE BEEN SELECTED AND CONTROLLED IN ACCORDANCE WITH SPAR-RHS-PA.003. THIS DOCUMENT DEFINES THE PROGRAM REQUIREMENTS FOR MONITORING AND CONTROLLING EEE PARTS. THE REQUIREMENTS INCLUDE PARTS SELECTION TO AT LEAST "ESTABLISHED RELIABILITY" LEVELS, AND ADEQUATE DERATING OF PART STRESS LEVELS. PROCEDURES AND ACTIVITIES ARE SPECIFIED TO ENSURE AT LEAST EQUIVALENT QUALITY FOR NONSTANDARD AND IRREGULAR PARTS. RELIABILITY ANALYSIS HAS CONFIRMED NO PARTS WITH GENERALLY HIGH FAILURE RATES. AEROSPACE DESIGN STANDARDS FOR DETAILING ELECTRONIC PARTS PACKAGING, MOUNTING AND STRUCTURAL/MECHANICAL/INTEGRITY OF ASSEMBLIES ARE APPLIED. SUCH DESIGN HAS BEEN REVIEWED AND FOUND SATISFACTORY THROUGH THE DESIGN AND IT PROCESS, INCLUDING THE USE OF RELIABILITY, MAINTAINABILITY AND SAFETY CHECKLISTS. MATERIAL SELECTION AND USAGE CONFORMS TO SPAR-RS.300 WHICH IS EQUIVALENT TO THE NASA MATERIALS USAGE REQUIREMENTS. WORST CASE ANALYSIS HAS BEEN CONDUCTED TO ENSURE THAT PERFORMANCE CAN BE MET UNDER WORST CASE TEMPERATURE AND AGING EFFECTS. EEE PARTS STRESS ANALYSIS HAS BEEN COMPLETED AND CONFIRMS THAT THE PARTS MEET THE DERATING REQUIREMENTS. PRINTED CIRCUIT BOARD DESIGNS HAVE BEEN REVIEWED TO ENSURE ADEQUATE CIRCUIT PAIN WIDTH AND SEPARATION AND TO COMPLY APPROPRIATE DIMENSIONS OF CIRCUIT SOLDER PADS AND OF COMPONENT MOUNT PROVISIONS. PARTS MOUNTING METHODS ARE CONTROLLED IN ACCORDANCE WITH NSFC-510-136 AND EAE PD91489. THESE DOCUMENTS REQUIRE APPROVED MOUNTING METHODS, STRESS RELIEF, AND COMPONENT SECURITY. WHERE APPLICABLE, DESIGN DRAWINGS AND DOCUMENTATION GIVE CLEAR IDENTIFICATION OF HANDLING PRECAUTIONS FOR ESD SENSITIVE PARTS. BOARD ASSEMBLY DRAWINGS INCLUDE THE REQUIREMENTS FOR SOLDERING STANDARDS IN ACCORDANCE WITH WRB 5300.613A) AND JSC 08800A.

CRITICAL ITEMS LIST

PROJECT: RMS

ASS'Y NOMENCLATURE: D&C PANEL

SYSTEM: D&C SUBSYSTEM

ASS'Y P/N: 51100391

SHEET: 2

ITEM REF.	REV.	NAME, QTY, & DRAWING REF. DESIGNATION	FAILURE MODE AND CAUSE	PATTERN EFFECT ON END ITEM	NO. OF FUNC. 1/1 CRITICALITY	RATIONALE FOR ACCEPTANCE
1130	0	DIRECT DRIVE COMMANDS QTY: 1 REP. SIGNAL CIRCUIT ED07315	MODE: LOSS OF 12.6V SIGNAL. EMUSE(5): (1) ZENER S/C (UPPER ZENER)	12.6V SIGNAL (+ DRIVE) WILL BE SHORTED TO 4.2V. JOINTS WILL DRIVE 'NEG' FOR 'POS' OR 'NEG' COMMAND. WORST CASE UNEXPECTED MOTION, WRONG JOINT DIRECTION, UNANNUNCIATED, CREW ACTION REQ. REDUNDANT PATHS REMAINING N/A	1/1	<p>ACCEPTANCE TESTS</p> <p>THE HARDWARE ITEM IS SUBJECT TO THE FOLLOWING ACCEPTANCE ENVIRONMENTAL TESTING AS PART OF THE D&C PANEL.</p> <p>Q VIBRATION: LEVEL AND DURATION - REFERENCE TABLE 1</p> <p>Q THERMAL: +100 DEGREES F TO +10 DEGREES F 2 CYCLES (9.5 HRS PER CYCLE)</p> <p>THE D&C PANEL ASSEMBLY IS FURTHER TESTED AS PART OF THE RMS SYSTEM (TP518 RMS STRONGBACK TEST AND TP552 FLAT FLOOR TEST) WHICH VERIFIES THE ABSENCE OF THE FAILURE MODE.</p> <p>QUALIFICATION TESTS</p> <p>THE D&C PANEL HAS BEEN SUBJECT TO THE FOLLOWING QUALIFICATION TEST ENVIRONMENT:</p> <p>Q VIBRATION: LEVEL AND DURATION - REFERENCE TABLE 1</p> <p>Q SHOCK: 20G/11MS - 3 AXES (6 DIRECTION)</p> <p>Q THERMAL: 130 DEGREES F TO -23 DEGREES F (12 HRS PER CYCLE) (6 CYCLES)</p> <p>Q HUMIDITY: 95% (120 DEGREES F TO 82 DEGREES F CYCLE IN 16 HRS) 90 CYCLES TOTAL</p> <p>Q EMC: MIL-STD-461 AS MODIFIED BY DA-E-0002 (TEST CR01, CE CR03, CS01(DC/AC), CS02, CS06, REB2 (B/N), RS02, RS03, RS44) RED2 (B/N) RS02, 03, 04)</p> <p>FLIGHT CHECKOUT</p> <p>PURS OPE CHECKLIST (ALL VEHICLES) JSC 14987</p>

PREPARED BY: H/WG

SUPERSEDING DATE: 11 SEP 86

APPROVED BY:

DATE:

CRITICAL ITEMS LIST

PROJECT: SAMS
ASS'Y NOMENCLATURE: DDC PANEL

SYSTEM: DDC SUBSYSTEM
ASS'Y P/N: 51100301

SHEET: 2

ITEM REF.	REV.	NAME QTY & DRAWING REF. DESIGNATION	FAILURE MODE AND CAUSE	FAILURE EFFECT ON END ITEM	HOW / WHEN / 1/1 CRITICALITY	RATIONALE FOR ACCEPTANCE
1130	0	DIRECT DRIVE COMMANDS QTY-1 REF. SIGNAL CIRCUIT EDB7395	MODE: LOSS OF 12.4V SIGNAL. CAUSE(S): (1) ZENER S/C (UPPER ZENER)	12.4V SIGNAL (+ DRIVE) WILL BE SHORTED TO 0.2V. JORM'S WILL BELIEVE 'NEG' FOR 'POS' OR 'NEG' COMMAND. WORST CASE UNEXPECTED MOTION. WRONG JOINT DIRECTION. UNANNOUNCED. CREW ACTION REQ. REDUNDANT PATHS REMAINING N/A		QA/INSPECTIONS EEE PARTS INSPECTION IS PERFORMED AS REQUIRED BY SPAR-RMS-PA.003. EACH EEE PART IS QUALIFIED AT THE PART LEVEL TO THE REQUIREMENTS OF THE APPLICABLE SPECIFICATION. ALL EEE PARTS ARE 100% SCREENED AND BURNED IN, AS A MINIMUM, AS REQUIRED BY SPAR-RMS-PA.003, BY THE SUPPLIER. ADDITIONALLY, EEE PARTS ARE 100% RE-SCREENED IN ACCORDANCE WITH REQUIREMENTS, BY AN INDEPENDENT SPAR APPROVED TESTING FACILITY. DPA IS PERFORMED AS REQUIRED BY PA.003 ON A RANDOMLY SELECTED 5% OF PARTS, MINIMUM 5 PIECES, MINIMUM 3 PIECES FOR EACH LOT NUMBER/DATE CODE OF PARTS RECEIVED. WIRE IS PROCURED TO SPECIFICATION MIL-W-22759 OR MIL-W-81381 AND INSPECTED AND TESTED TO NASA J52M0008 STANDARD NUMBER 95A. RECEIVING INSPECTION VERIFIES THAT ALL PARTS RECEIVED ARE AS IDENTIFIED IN THE PROCUREMENT DOCUMENTS, THAT NO PHYSICAL DAMAGE HAS OCCURRED TO PARTS DURING SHIPMENT, THAT THE RECEIVING DOCUMENTS PROVIDE ADEQUATE TRACEABILITY INFORMATION AND SCREENING DATA CLEARLY IDENTIFIES ACCEPTABLE PARTS. PARTS ARE INSPECTED THROUGHOUT MANUFACTURE AND ASSEMBLY AS APPROPRIATE TO THE MANUFACTURING STAGE COMPLETED. THESE INSPECTIONS INCLUDE, PRINTED CIRCUIT BOARD INSPECTION FOR TRACK SEPARATION, DAMAGE AND ADEQUACY OF PLATED THROUGH HOLES, COMPONENT MOUNTING INSPECTION FOR CORRECT SOLDERING, WIRE LOOPING, STRAPPING, ETC. OPERATORS AND INSPECTORS ARE TRAINED AND IDENTIFIED TO NASA HND 5300.413A1 STANDARD, AS MODIFIED BY JSC OORDBA. CONFORMAL COATING INSPECTION FOR ADEQUATE PROCESSING IS PERFORMED USING ULTRAVIOLET LIGHT TECHNIQUES. POST P.C. BD. INSTALLATION INSPECTION, CLEANLINESS AND WORKMANSHIP (SPAR/GOVERNMENT REP. MANDATORY INSPECTION POINT) P.C. BD. INSTALLATION INSPECTION, CHECK FOR CORRECT BOARD INSTALLATION, ALIGNMENT OF BOARDS, PROPER CONNECTION CONTACT MATING, WIRE ROUTING, STRAPPING OF WIRES ETC., PRE-TEST INSPECTION OF DDC PANEL ASSY INCLUDES AN AUDIT OF LOWER TIER INSPECTION COMPLETION, AS BUILT CONFIGURATION VERIFICATION TO AS DESIGN ETC. (SPAR/GOVERNMENT REP. MANDATORY INSPECTION POINT) A TEST READINESS REVIEW (TRR) WHICH INCLUDES VERIFICATION OF TEST PERSONNEL, TEST DOCUMENTS, TEST EQUIPMENT CALIBRATION/ VALIDATION STATUS AND HARDWARE CONFIGURATION IS CONVENED BY QUALITY ASSURANCE IN CONJUNCTION WITH ENGINEERING, RELIABILITY, CONFIGURATION CONTROL, SUPPLIER AS APPLICABLE, AND THE GOVERNMENT REPRESENTATIVE, PRIOR TO THE START OF ANY FORMAL TESTING (ACCEPTANCE OR QUALIFICATION). ACCEPTANCE TESTING (ATP) INCLUDES AMBIENT PERFORMANCE.

PREPARED BY: NENG

DATE: 11 SEP 86

APPROVED

CRITICAL ITEMS LIST

PROJECT: SRMS
ASS'Y NOMENCLATURE: D&C PANEL

SYSTEM: D&C SUBSYSTEM
ASS'Y P/N: 511406197

SHEET 4

P/N REF.	REV.	NAME, QTY, & DRAWING REF. DESIGNATION	FAILURE MODE AND CAUSE	FAILURE EFFECT ON END ITEM	FORM / PLWC, 1/1 CRITICALITY RATIONALE FOR ACCEPTANCE
1150	0	DIRECT DRIVE COMMANDS QTY-1 REF. SIGNAL CIRCUIT 6087315	MODE: LOSS OF 12.4V SIGNAL. CAUSE(S): (1) ZENER S/C (UPPER ZENER)	12.4V SIGNAL (+ DRIVE) WILL BE SHORTED TO 6.2V. JOINTS WILL DRIVE 'NEG' FOR 'POS' OR 'NEG' COMMAND. WORST CASE UNEXPECTED MOTION. WRONG JOINT DIRECTION. UNANNUNCIATED. CREW ACTION REQ. REDUNDANT PATHS REMAINING N/A	THERMAL AND VIBRATION TESTING, (SPAR/GOVERNMENT REP. - MANDATORY INSPECTION POINT). INTEGRATION OF D&C PANEL, RMC, THE AND MC1U, INSPECTIONS ARE PERFORMED AT EACH STAGE OF INTEGRATION, WHICH INCLUDES GROUNDING CHECKS, INTER CONNECT CABLE VERIFICATION, CONNECTOR INSPECTION FOR BENT OR PUSHBACK CONTACTS ETC. SUB-SYSTEM PERFORMANCE TESTING (ATP), INCLUDES AN AMBIENT PERFORMANCE TEST. (MANDATORY INSPECTION POINT). SRMS SYSTEMS INTEGRATION, IIR INTEGRATION OF MECHANICAL ARM SUBASSEMBLIES AND THE FLIGHT CABIN EQUIPMENT TO FORM THE SRMS. INSPECTIONS ARE PERFORMED AT EACH PHASE OF INTEGRATION WHICH INCLUDES GROUNDING CHECKS, THRU WIRING CHECKS, WIRING ROUTING, INTERFACE CONNECTORS FOR BENT OR PUSH BACK CONTACTS ETC. SRMS SYSTEMS TESTING - STRONGBACK AND FLAT FLOOR AMBIENT PERFORMANCE TEST. (SPAR/GOVERNMENT REP. - MANDATORY INSPECTION POINT)

PREPARED BY: NFMG

SUPERSEDING DATE: 11 SEP 86

APPROVED BY:

DATE

CRITICAL ITEMS LIST

PROJECT: RMS
 ASS'Y NOMENCLATURE: DDC PANEL

SYSTEM: DDC SUBSYSTEM
 ASS'Y P/N: 51100201

SHEET: 5

P/N REF.	REV.	PART, QTY & DRAWING REF. DESIGNATION	FAILURE MODE AND CAUSE	FAILURE EFFECT ON END ITEM	FORM / FUNC. I/I CRITICALITY	RATIONALE FOR ACCEPTANCE
1150	0	DIRECT DRIVE COMMAND QTY-1 REF. SIGNAL CIRCUIT E087315	MODE: LOSS OF 12.4V SIGNAL. CAUSE(S): (1) ZEMER S/C (UPPER ZEMER)	12.4V SIGNAL (+ BRAYE) WILL BE SHORTED TO 4.2V. JOINTS WILL DRIVE 'NEG' FOR 'POS' OR 'NEG' COMMAND. WORST CASE ----- UNEXPECTED MOTION, WRONG JOINT DIRECTION. UNANNOUNCED. CREW ACTION REQ. REDUNDANT PATHS REMAINING ----- N/A	FAILURE HISTORY -----	NO EEE PARTS FAILURES HAVE OCCURRED SUBSEQUENT TO ASSEMBLY OF PARTS.

PREPARED BY: HMG

SUPERSEDING DATE: 11 SEP 86

DATE:

CRITICAL ITEMS LIST

PROJECT: SRMS
 ASS'Y NOMENCLATURE: ODC PANEL

SYSTEM: ODC SUBSYSTEM
 ASS'Y P/N: 511400391

SHEET: 62

PREA REF.	REV.	NAME, QTY & DRAWING REF. DESIGNATION	FAILURE MODE AND CAUSE	FAILURE EFFECT ON END ITEM	HMMR / FUNC. I/F CRITICALITY	RATIONALE FOR ACCEPTANCE
1430	1	DIRECT DRIVE COMMANDS QTY-1 REC. SIGNAL CIRCUIT (ORT315)	MODE: LOSS OF 12.4V SIGNAL. CAUSE(S): 1) ZERO S/C (UPPER ZERO)	12.4V SIGNAL (+ BRINE) WILL BE SHORTED TO G. 2V. JOINTS WILL BRINE 'NEG' FOR 'POS' OR 'NEG' COMMAND. WORST CASE UNEXPECTED MOTION, BRING JOINT DIRECTION, UNANNUNCIATED. CREW ACTION REQ. REDUNDANT PATHS REMAINING N/A		<p>OPERATIONAL EFFECTS</p> <p>JOINT DOES NOT RESPOND PROPERLY TO COMMANDS IN DIRECT MODE.</p> <p>CREW ACTION</p> <p>REMOVE COMMAND.</p> <p>CREW TRAINING</p> <p>THE CREW SHOULD BE TRAINED TO ALWAYS OBSERVE WHETHER THE ARM IS RESPONDING PROPERLY TO COMMANDS. IF AT RSM'T, THE COMMAND SHOULD BE REMOVED.</p> <p>MISSION CONSTRAINT</p> <p>OPERATE AT LESS THAN VERNIER RATES WITHIN 10 FT OF STRUCTURE BY CYCLING SWITCH. OPERATOR MUST BE ABLE TO DETECT THAT THE ARM IS RESPONDING PROPERLY TO COMMANDS VIA WINDOW AND/OR CCTV VIEWS DURING ALL ARM OPERATIONS.</p> <p>SCREEN FAILURES</p> <p>N/A</p> <p>OMRSD OFFLINE</p> <p>EXERCISE DIRECT DRIVE SWITCH VERIFY VOLTAGE ON DIRECT DRIVE HARDWARE LINES AT ODC PANEL OUTPUT</p> <p>OMRSD ONLINE INSTALLATION</p> <p>EXERCISE DIRECT DRIVE SWITCH VERIFY VOLTAGE ON DIRECT DRIVE HARDWARE LINES AT LONGERON INTERFACE</p> <p>OMRSD ONLINE TURNAROUND</p> <p>EXERCISE DIRECT DRIVE COMMANDS VERIFY CORRECT JOINT MOTOR RESPONSES</p>

PREPARED BY: HMG

SUPERSEDING DATE: 05 OCT 07

APPROVED BY: _____

DATE: _____