CIL

EMU CRITICAL ITEMS LIST

5/30/2002 SUPERSEDES 12/24/1991

Page 1

Date: 4/24/2002

NAME		FAILURE		
P/N QTY	CRIT	MODE & CAUSES	FAILURE EFFECT	RATIONALE FOR ACCEPTANCE
		138FM04A		
PRESSURE TRANSDUCER, FEEDWATER, ITEM 138 SV767793-6 (1)	2/1R	External water leakage. Housing seal failure.	END ITEM: Water leakage to ambient when 137 feedwater valve is open.	A. Design - -2 and -6 Conrac and -8 Gulton: The external leak path for the primary pressure sensor is through a static radial 0-seal. The seal groove configuration and rigidness of assembly provide squeeze under all tolerance and envrionmental conditions. The temperature and pressure are not extreme (32 deg. F to 120 deg. F and 20 psid max. respectively).
PRESSURE TRANSDUCER, FEEDWATER, ITEM 138 SV767793-8 (1)			GFE INTERFACE: Depletion of the water reservoir. Loss of cooling/ defog. MISSION: Terminate EVA when the water supply drops below CWS limits. CREW/VEHICLE: None for single failure. Possible loss of crewman with loss of SOP.	 B. Test - Component Acceptance Test - Conrac and Gulton: The Feedwater pressure sensor is subjected to acceptance testing prior to shipment by the assembly vendor. This testing includes the following tests which insure there is no external leak path at the sensor port: Proof pressure testing to a pressure of 24 psia for one minute using fixture which simulates the sensor installation in the PLSS. Calibration check of sensor to 16 psia, using a fixture which simulates the sensory installation. PDA Test - The feedwater pressure sensor undergoes proof, leakage and performance testing per SEMU-60-010 after installation on the PLSS. Certification Test - Certified for a useful life of 20 years (Ref. EMUM1-0084). C. Inspection - The sensor port configuration is visually and dimensionally inspected to B/P requirements to insure there will not be any leakage paths. D. Failure History - None.
			TIME TO EFFECT /ACTIONS: Minutes. If there is insufficient water for cooling/ defog, open purge valve to activate the SOP. TIME AVAILABLE: Minutes. TIME REQUIRED: Seconds.	 E. Ground Turnaround - None. F. Operational Use - Crew Response - EVA: When CWS data confirms activation of reserve water tank, terminate EVA. Training - Standard EMU training covers this failure mode. Operational Considerations - Flight rules require termination of EVA when minimum primary consumables remain. EVA checklist procedures verify hardware integrity and systems operational status prior to EVA. Real Time Data System allows ground monitoring of EMU systems.

CIL EMU CRITICAL ITEMS LIST			5/30/2002 SUPERSEDES 12/24/1991		Page 2 Date: 4/24/2002
NAME P/N QTY	CRIT	FAILURE MODE & CAUSES	FAILURE EFFECT	RATIONALE FOR ACCEPTANCE	
		138FM04A	REDUNDANCY SCREENS: A-PASS B-PASS C-PASS		

EXTRAVEHICULAR MOBILITY UNIT

SYSTEMS SAFETY REVIEW PANEL REVIEW

FOR THE

I-138 FEEDWATER PRESSURE SENSOR

CRITICAL ITEM LIST (CIL)

EMU CONTRACT NO. NAS 9-97150

Prepared by: HS - Project Engineering

HS -

d 4/24/02 HS - Engineering Manager

Approved by: ______ MASA

25

SAMMOL

NASA Crew

NASA Wogram Manager