CIL

EMU CRITICAL ITEMS LIST

## 5/30/2002 SUPERSEDES 12/31/2001

Page 1

Date: 6/21/2002

			12/31/20	01
NAME P/N QTY	CRIT	FAILURE MODE & CAUSES	FAILURE EFFECT	RATIONALE FOR ACCEPTANCE
		391FM09		
JUMPER HARNESS, ITEM 391	2/2	Electrical open in	END ITEM: Low continuity	A. Design - Open circuits are minimized by the following:
SV821755-1 (1)		battery sense + or - line.  Cable chafing against connector shell or shield.	in CWS battery volage sense lines.  GFE INTERFACE: Battery voltage sensor reads zero	Each connector/adapter ring interface is locked in place to prevent rotation by a mechanical lock. #22 AWG Teflon insulated wires and connector provide electrical conduction and insulation properties. Connector pins are operating at 56.7% of derated temperature and wire at 89.4% of derated current. The woven Halar sheath is assembled over the internal cables to provide protection from abrasion and impact. The P3 connector backshell housing has internal edges blended smooth to prevent cable chafing. Strain relief is provided by the combination of convolute tubing, metal EMI braid, and 0.5" extra cable length.
		Improper connector strain relief. Faulty	volts. BATT VDC LOW, BATT VDCC XX.X warning	The braided items are secured by a band strap at each connector/cable interface. The convolute tubing is threaded into the connectors. Wire crimping is performed per SVHS4909 (based on MSFC Spec-Q-1A).
		connection between the	message issued.	B. Test - Component Acceptance Test -
		connector and the lead wires, insulation breakdown, conductor severed, contact resistance.	MISSION: False warning that battery has failed. Terminate EVA.	The 391 harness is subjected to acceptance testing per AT-E-391 prior to final acceptance to ensure there are no workmanship problems that could cause an open or short circuit. Each connector/harness interface is subjected to a 9-lb. pull test. The insulation resistance between each conductor and the ground circuit is measured during this test to ensure there are no intermittent shorts and to
			CREW/VEHICLE: None.	verify the integrity of the harness strain relief. A continuity test is performed to measure the resistance of each circuit to ensure there are no open circuits or high resistance paths. The insulation resistance and dielectric strength between each conductor and the shield ground is measured to ensure there are no shorts.
			TIME TO EFFECT /ACTIONS: Seconds.	PDA Test - The SSER battery sense (+) or (-) is checked during DCM PDA testing per SEMU-60- 015 para. 4.0 (Electrical Testing).
			TIME AVAILABLE: N/A	Certification Test - Certified for a useful life of 15 years (ref. EMU1-13-046).
			TIME REQUIRED:	C. Inspection -
			N/A	To ensure that there are no workmanship problems which could cause an open circuit in the harness conductors, the following inspections are made: Contact
			REDUNDANCY SCREENS: A-N/A B-N/A C-N/A	crimp samples are made prior to start of crimping and at the conclusion of crimping and pull tested to ensure the crimp tooling is operating properly. All crimp terminations are inspected for defects. Harness cables and conductors are visually inspected prior to assembly to ensure there are no defects which could cause an open due to workmanship. Electrical bond test is performed to verify ground path through various points on the harness. In-process and final
				ground path through various points on the harness. In-process and final electrical checkout of the harness (conductor continuity, dielectric strength,

D. Failure History - None.

circuits.

E. Ground Turnaround Tested for non-EET processing per FEMU-R-001, Final Pre-Flight Communications.
FEMU-R-001, Para. 8.2, EMU Pre-flight KSC Checkout for EET processing.

and insulation resistance tests) are performed to ensure there are no open/short

CIL Page 2

5/30/2002 SUPERSEDES 12/31/2001

NAME FAILURE
P/N MODE &

FAILURE EFFECT

391FM09

CAUSES

EMU CRITICAL ITEMS LIST

CRIT

QTY

F. Operational Use -

RATIONALE FOR ACCEPTANCE

Crew Response - Pre-EVA: Troubleshoot problem. Consider third EMU if available. If no success, terminate EVA prep. EVA: When battery low voltage message occurs, terminate EVA.

Operational Considerations -

Flight rule A15.1.2-2 of "Space Shuttle Operational Flight Rules", NSTS-12820 defines go/no go criteria related to EMU battery power. Generic EVA Checklist, JSC-48023, procedures Section 3 (EMU Checkout) and 4 (EVA prep) verify hardware integrity and systems operational status prior to EVA. Real Time Data System allows ground monitoring of EMU systems.

Date: 6/21/2002

## EXTRAVEHICULAR MOBILITY UNIT

## SYSTEMS SAFETY REVIEW PANEL REVIEW

FOR THE

I-106 GLOVE ASSEMBLY

CRITICAL ITEM LIST (CIL)

EMU CONTRACT NO. NAS 9-97150

Prepared by:

Approved by: NASA – SSA/SSM